

## ABSTRACT

A communication distribution system having a coaxial cable distribution hub. A control panel box includes a plurality of removable modules selectively connectable to incoming phone lines, cable lines, antenna and satellite input lines and a computer CPU input line. The modules are arranged to allow the incoming lines to be selectively connectable to various rooms in a building. The coaxial cable distribution hub includes intermediate coaxial cable room connectors. An indicia wall next to the intermediate coaxial cable connectors includes a room chart for marking and assigning a particular room outlet with the coaxial connector.